



Contents

Part I: Main Technical Parameters

Part II: Configuration

Part III: Quotation

Part IV: Remarks

Part I: Main Technical Parameters

Model	HZS35
Productivity (m3/h)	35
cycle time (s)	72
Amount power (KW)	80
Mixer model	JS750
Batching machine model	PLD1200
Feeding model	Lift Hopper
Discharge height (m)	3.8-4.2
Air compressor model	7.5KW
water weighing accuracy	±1%
Aggregate weighting accuracy	±2%
Cement weighing accuracy	±1%
Overall size Working position L*W*H (mm)	18360×9800×17600

Part II: Configuration

No	Product name		Specification/ Model	Quantity	
1	Batching system	Aggregate bin (5m3)	PLD1200	2set	
		Measuring belt		1 set	
		Measuring sensor		1 set	
		Belt conveyor		3 set	
					
2	Mixing system	Mixer	JS750	1 set	
		Lubrication system	Thick oil pump	1 set	
		Discharge system	pneumatic	1 set	
		Wearing plate	Hard-wearing	1 set	
		Hoisting Mechanism	Aggregate lift hopper	1 set	
		Lift hopper		1 set	
		Rail rack		1 set	
					
3	Water weighing system	Water flow-meter		1 set	
		Water pump		1 set	
		Pipe valve system		1 set	
	Cement	Cement weighing bin		1 set	

4	weighing system	Cement weigher		1 set	
		Butterfly valve		1 set	
5	Additive weighing system	Additive weighing bin		1 set	
		Pipeline		1 set	
		Weighing sensor		1 set	
		Butterfly valve		1 set	
					
6	Pneumatic system	Air compressor		1 set	
		electromagnetic valve		1 set	
		Pipeline system		1 set	
					
7	Electric control system	current cabinet		1 set	
		Control computer		1 set	
		Contactor		1 set	
		Autoswitch		1 set	
		Mini-relay		1 set	
		Termo-relay		1 set	
		Weighing transmitter		1 set	
		Electrical control accessories		1 set	

					
8	Screw conveyor		ø219	1 set	
9	Cement Pot		100T	1 set	

Part III: Quotation

1	HZS50 concrete batching plant	Item 1-9
2	Quantity	1 set
3	Container need	1*40HQ
4	EXW	25500 \$
5	Delivery time	15 working days after 30% deposit confirmed
6	Payment terms	30% advanced payment, 70% before delivery
7	Color	As request

Part IV: Remarks

Warranty period: 15 months after shipment.

Validity period of quotation: 30 days.

Installation and Debugging:

- 1, We shall send two technicians to the site to provide guidance on installation & debugging and training of the operators;
- 2, Engineers round-trip air tickets, visa application fee, board and lodging expenses are paid by the buyer;
- 3, Engineers one day salary 80usd.