



Zhengzhou Hualong Construction Machinery Co.,Ltd



Contents

Part I: Main Technical Parameters

Part II: Configuration

Part III: Quotation

Part IV: Remarks

Part I: Main Technical Parameters

Model	HZS120
Productivity (m3/h)	120
cycle time (s)	60
Amount power (KW)	200
Mixer model	JS2000
Batching machine model	PLD3200
Feeding model	Lift Hopper
Discharge height (m)	4.0-4.5
Air compressor model	HTA-100
water weighing accuracy	±1%
Aggregate weighing accuracy	±2%
Cement weighing accuracy	±1%
Overall size Working position L*W*H (mm)	36000×18000×17600

Part II: Configuration

No	Product name		Specification/Model	Quantity	notes
1	Batching system	Aggregate bin (15m3)	PLD3200	4 set	
		Measuring belt		1 set	
		Measuring sensor		1 set	
		Roller motor		1 set	
					
2	Mixing system(JS 2000)	Mixer	JS2000	1 set	
		Lubrication system	Thick oil pump	1 set	
		Discharge system	pneumatic	1 set	
		Wearing plate	Hard-wearing	1 set	
		Rail rack		1 set	
					
3	Belt conveyor	Roller motor		1 set	
		Rubber conveyor belt		1 set	
		Buffer hopper		1 set	
		Belt conveyor frame		1 set	
		Various idlers		1 set	

					
4	Water weighing system	Water flow-meter		1 set	
		Water pump		1 set	
		Pipe valve system		1 set	
5	Cement weighing system	Cement weighing bin		2set	
		Cement weigher		2set	
		Butterfly valve		2set	
6	Additive weighing system	Additive weighing bin		1 set	
		Pipeline		1 set	
		Weighing sensor		1 set	
		Butterfly valve		1 set	
					
7	Pneumatic system	Air compressor		1 set	
		electromagnetic valve		1 set	
		gasholder		1 set	
		Pipeline system		1 set	
					
		current cabinet		1 set	

8	Electric control system	Control computer		1 set	
		Contactor		1 set	
		Autoswitch		1 set	
		Mini-relay		1 set	
		Thermo-relay		1 set	
		Strong electric cabinet		1 set	
		Weighing transmitter		1 set	
		Electrical control accessories		1 set	
 					
9	Screw conveyor		ø273 *9m	1 set	
10	150T Flaky cement silo	Cone part of cement soil		1 set	
		Cylinder part of cement soil		1 set	
		Electric precipitator		1 set	
		Accessories		1 set	
  					

Part III: Quotation

1	HZS120 concrete batching plant	Item 1-11
2	Quantity	1 set
3	Container need	45HQ+40
4	EXW PRICE	63000 \$
5	Delivery time	15 working days after 30% deposit confirmed
6	Payment terms	30% advanced payment, 70% before delivery
7	Color	As request

Part IV: Remarks

Warranty period: 15 months after shipment.

Validity period of quotation: 30 days.

Installation and Debugging:

1, We shall send two technicians to the site to provide guidance on installation & debugging and training of the operators;

2, Engineers round-trip air tickets, visa application fee, board and

lodging expenses are paid by the buyer;

3, Engineers one day salary 100usd.